

Cellulose Retrofit Addendum

EXTERIOR SIDING REMOVAL & DENSE-PACK

This Addendum supplements the General Contract & Terms and the attached estimate. It applies to retrofit insulation work performed by removing exterior siding to access enclosed wall cavities. Where this Addendum conflicts with the General Contract, this Addendum controls.

1. SCOPE OF RETROFIT WORK

Green Idea Insulation will remove select courses of exterior siding, drill access holes in the sheathing, dense-pack the wall cavities with cellulose insulation, plug the access holes, and reinstall the removed siding. Areas and quantities are as described in the attached estimate.

2. ASBESTOS-CONTAINING MATERIALS

Asbestos cement siding and other asbestos-containing materials are common in homes built before 1980. Green Idea Insulation does not test for, disturb, remove, or dispose of asbestos-containing materials. If suspected asbestos is encountered, work in that area stops immediately and the customer is responsible for engaging a licensed asbestos contractor before work resumes. Delays and additional mobilization caused by this are not included in the contract price.

3. KNOB-AND-TUBE AND OTHER WIRING

Insulation must not be installed in contact with active knob-and-tube wiring. If knob-and-tube or other unsafe wiring is discovered in the cavities to be insulated, work in that area stops until the customer has the wiring evaluated and corrected by a licensed electrician. Electrical work is not included in this contract.

4. SIDING REMOVAL, BREAKAGE, AND MATCH

Siding is removed and reinstalled with reasonable care. However, existing siding — particularly aged vinyl, wood, and composite — can become brittle and may crack or break during removal despite proper technique. This is a normal condition of retrofit work and is not a defect in workmanship.

- Replacement pieces for broken siding are not included in the contract price unless expressly listed in the estimate.
- Discontinued profiles, colors, and textures may not be available. Green Idea Insulation does not guarantee an exact match for any replacement piece.
- Weathered siding fades over time; new or previously unexposed pieces will not match the surrounding color.

5. ACCESS HOLES, PLUGS, AND FINISH WORK

Access holes drilled in the sheathing are plugged and the siding is reinstalled over them. Painting, staining, caulking beyond what is needed to reinstall the siding, and any exterior finish work are not included unless expressly listed in the estimate.

6. EXISTING CONDITIONS AND HIDDEN DAMAGE

Retrofit work exposes conditions that cannot be seen during the estimate. Rot, water damage, insect damage, failed housewrap, missing sheathing, prior blockages, and similar pre-existing conditions are not the responsibility of Green Idea Insulation and are not included in the contract price. If such conditions are found, the customer will be notified and any corrective work will be quoted separately.

7. CAVITY OBSTRUCTIONS AND COVERAGE

Wall cavities may contain fire blocking, diagonal bracing, plumbing, ductwork, or existing insulation that limits fill. Additional access holes may be required to reach blocked sections. Cavities that cannot be accessed without disproportionate demolition will be identified to the customer and excluded from the scope.

8. DENSITY, SETTLING, AND R-VALUE

Cellulose is installed to manufacturer-recommended dense-pack density to resist settling. As stated in the General Contract, the material cannot be installed to exact depths, and this does not constitute a defect in materials or workmanship. R-values are based on the manufacturer's published coverage chart for the product installed.

9. SITE PROTECTION AND CLEANUP

Work areas are covered and protected during the work, and debris generated by Green Idea Insulation is removed at completion. The customer is responsible for clearing landscaping, furniture, vehicles, and stored items from the exterior work areas before the start date so that siding can be safely accessed.

Acknowledgement

By signing below, the customer acknowledges the retrofit conditions described in this Addendum, including those regarding asbestos, wiring, siding breakage, and color match, and agrees that these terms apply in addition to the General Contract & Terms and the attached estimate.

Customer: _____ Date: _____

Green Idea Insulation: _____ Date: _____